

DRAFT TENDER SCHEDULE

Item No. 46

Name of the Work : Improvements to Roads and Drains at (Near Narayanapura Road) Cauvery layout in Ward No.06, Byatarayanapura Sub Division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	747.38	KSRB 2-1.1: Earth work in surface excavation in ordinary soil for leveling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe line and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.5m, excavated surface leveled and neatly dressed, disposed earth to be leveled after breaking of clods and neatly dressed as per specifications, Specification No KBS 2.1(a) / 2.3.1,P. No. 5/ Item No. 2.1/ PWD SR 2011-12	cum	120.96	
2	162.97	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in Hard soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3/ PWD SR 2011-12	Cum	217.08	
3	985.50	Removing B.S Slab of Drain and stacking Page No. 28/ Item No. 5.32/ PWD SR 2011-12	Sqm	47.52	
4	985.50	Refixing stone slabs of drains and pointing in C.M (1:3) Page No. 28/ Item No. 5.33/ PWD SR 2011-12	Sqm	64.18	
5	1004.40	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar(1:6) including fixing curing etc, complete Page No. 28/ Item No. 5.31 / PWD SR 2011-12	Sqm	332.37	
6	1.30	KSRB 4-1.7 : : Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2/P No. 13/ Item No. 4.7/ PWD SR 2011-12	Cum	3939.41	
7	2.88	KSRB 5.2.3 Providing and constructing granite / trap / basalt Size stone masonry in foundation with cement mortar 1:6, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5.1.13 Page No. 25/ Item No. 5.6/ PWD SR 2011-12	Cum	2827.87	
8	1.92	KSRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:8, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 26/ Item No. 5.9/ PWD SR 2011-12	Cum	3300.91	

Sl. No.	Quantity.	Description	Unit	In Figures	Rates In Words
9	0.48 ✓	KSRB-4-1.6 : Providing and laying in position plain cement concrete of mix M15 with OPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/ P.No. 12/ Item No. 4.6/ PWD SR 2011-12	Cum	4462.34 ✓	
10	4.80 ✓	KSRB 15.2.1: Providing flush pointing to stone slab pavements, with cement mortar 1:3, after raking joints, nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 119/ Item No. 15.7/ PWD SR 2011-12	Sqm	26.70 ✓	
11	1.58 ✓	KSRB 4.2.2 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum with superplastesisre @ 3lts conforming to IS9103-1999Reffirmed machine mixed exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls(any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour HOM of machinery, curing, complete as per specifications. Specification. No. KBS 4.1,4.6, No. KBS 4.1,4.6, No. 13/ Item No. 4.11/ PWD SR 2011-12	Cum	5296.75 ✓	
12	1.43 ✓	KSRB 4.9.2:providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost pf materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19/ Item No. 4.46/ PWD SR 2011-12	Qtl	7347.82 ✓	
13	362.74 ✓	KSRRB M400-14.2: Providing, laying, spreading and compacting stone aggregates of specific size to water bound macadam specifications. Including spreading in uniform thickness, hand packing, rolling with 3-whelled steel / vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening / binding materials to fill up the interstices of coarse aggregates, watering and compacting to the required density complete as per specifications. B by mechanical means, MORTH specification No. 404, Crushable type such as moorum or gravel for grading II , No. 166/ Item No. 20.15.2/ PWD SR 2011.12	Cum	1072.44 ✓	

ಕರಡು ಚಂದರ್ ಪದ್ಮೋನ್ಯ
ತಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ
ತಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ.


ಶಿಕ್ಷಣಾಧಿಕಾರಿ/ಪ್ರಾಂಶುಪಾಲರು
ಆರೋಗ್ಯ ಮತ್ತು
ವಿದ್ಯಾರಣ್ಯಾಧಿಕಾರಿಗಳು


Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92